


TRUSS 2T1 SCHEMATIC

BILL OF MATERIAL							BILL OF MATERIAL						
LIFT NO.	LIFT QTY.	NO. OF PIECES	MARK	MATERIAL	LENGTH FT. IN.	WEIGHT TOTAL	LIFT NO.	LIFT QTY.	NO. OF PIECES	MARK	MATERIAL	LENGTH FT. IN.	WEIGHT TOTAL
		2	271	TRUSS		25635			2	a127	L5x5x $\frac{3}{8}$	8	4 $\frac{3}{4}$
		2	w77	M8x58	59	1 $\frac{3}{8}$			2	a75	L5x5x $\frac{3}{8}$	8	4 $\frac{3}{4}$
		4	a67	L4x4x $\frac{3}{8}$	1	9			2	a106	L5x5x $\frac{3}{8}$	5	7 $\frac{1}{2}$
		4	a65	L4x4x $\frac{3}{8}$	0	5 $\frac{3}{4}$			2	a43	L5x5x $\frac{3}{8}$	5	7 $\frac{1}{2}$
		2	p112	PL1x30	3	1			2	a135	L5x5x $\frac{3}{8}$	5	5
		2	p151	PL1x26	2	9 $\frac{1}{2}$			2	a46	L5x5x $\frac{3}{8}$	5	5
		2	p139	PL1x26	2	8			2	a103	L4x4x $\frac{3}{8}$	5	2 $\frac{1}{2}$
		2	p148	PL1x25	2	6 $\frac{1}{4}$			2	a47	L4x4x $\frac{3}{8}$	5	2 $\frac{1}{2}$
		2	p153	PL1x16	2	0			2	a138	L4x4x $\frac{3}{8}$	5	10 $\frac{1}{2}$
		4	p159	PL1x16	2	0			2	a78	L4x4x $\frac{3}{8}$	5	10 $\frac{1}{2}$
		2	p161	PL1x8	1	8			2	a108	L4x4x $\frac{3}{8}$	5	5
		2	w129	M8x58	58	3 $\frac{1}{2}$			2	a59	L4x4x $\frac{3}{8}$	5	5
		2	p125	PL1x30	3	1 $\frac{1}{4}$			2	a110	L5x5x $\frac{3}{8}$	5	7 $\frac{1}{2}$
		2	p150	PL1x26	2	9 $\frac{1}{2}$			2	a53	L5x5x $\frac{3}{8}$	5	7 $\frac{1}{2}$
		2	p152	PL1x26	2	9 $\frac{1}{2}$			2	a112	L5x5x $\frac{3}{8}$	5	2 $\frac{1}{2}$
		2	p142	PL1x26	2	9 $\frac{3}{8}$			2	a55	L5x5x $\frac{3}{8}$	5	2 $\frac{1}{2}$
		2	p141	PL1x26	2	9							
		2	p160	PL1x20	3	11 $\frac{1}{4}$							
		2	p156	PL1x16	2	0			8	1 Dia A490N	0	3 $\frac{1}{2}$	1HD WASH
		8	p208	PL $\frac{1}{2}$ x7	0	8			12	1 Dia A490N	0	3	1HD WASH
		2	a133	L5x5x $\frac{3}{4}$	7	3 $\frac{3}{8}$			24	1 Dia A325N	0	3	1HD WASH
		2	a132	L5x5x $\frac{3}{4}$	7	3 $\frac{3}{8}$			16	$\frac{3}{4}$ Dia A325N	0	2	1HD WASH
		2	a134	L5x5x $\frac{3}{8}$	8	3 $\frac{3}{8}$							
		2	a129	L5x5x $\frac{3}{8}$	8	3 $\frac{3}{8}$							
		2	a136	L4x4x $\frac{1}{2}$	7	10 $\frac{3}{8}$							
		2	a72	L4x4x $\frac{1}{2}$	7	10 $\frac{3}{8}$							
		4	a137	L3 $\frac{1}{2}$ x3 $\frac{1}{2}$ x $\frac{1}{2}$	8	1 $\frac{1}{8}$							
		4	a73	L3 $\frac{1}{2}$ x3 $\frac{1}{2}$ x $\frac{1}{2}$	8	1 $\frac{1}{8}$							
		2	a128	L4x4x $\frac{1}{2}$	8	4 $\frac{3}{8}$							
		2	a74	L4x4x $\frac{1}{2}$	8	4 $\frac{3}{8}$							



MATCHLINE
SHEET 2T1a
MATCHLINE
SHEET 2T1b

2 TRUSSES 2T1

HOLES: 1 $\frac{3}{16}$ " DIA U.N.D.
SURFACE PREP: SSPC-SP 2
FINISH: 1 SHOP COAT PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.
ALL COPIES TO HAVE $\frac{1}{2}$ " MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY
MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E.DWG
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

print record	1-5	1-27
1	APP	FAB

job no. 404-100
date 1-1-12
drawn by MC
check by GJ

revisions	description
rev#	date


STEEL AND ENGINEERING COMPANY
P.O. BOX 104-598 ROUTE #22
PLATTSBURGH, N.Y. 12001
518-561-4061

JEFFORDS

LORAN CONSTRUCTION INC
286 STATE HIGHWAY 37
HOGANSBURG, NY

AKWESASNE MOHAWK CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY



sheet
2T1a

[illegible]

HOLES:	13/16" DIA U.N.O.
SURFACE PREP:	SSPC-SP 2
FINISH:	1 SHOP COAT PPG COATING 94-232
ELECTRODES:	E70XX-(LOW HYDROGEN)
GENERAL NOTES:	
ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.	
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.	
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.	
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY	
MEMBERS ARE TO BE ERRECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E Dwg	
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.	


sheet

2T1b




ONE COLUMN 11C15

W 9 3/4 x 5 1/8
F 7 15/16 x 7 1/8
K 1 1/8 x 13 1/8



Section C-C

11C15



Section B-B

11C15



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
11	1	ONE	11C15	COLUMN	16	0 3/4	MIE A992	765
			2	p322	0	8 3/4	A572-50	31
			2	p329	0	4 3/8	A572-50	12
			2	p331	0	3 13/16	A572-50	10
			2	p301	0	8 3/4	A572-50	21
			1	p515	1	4	A572-50	53
			2	p336	2	1 1/4	A572-50	67
			1	p297	1	10 1/4	A572-50	20
			1	p307	1	10 1/4	A572-50	23

HOLES: 13/16" DIA U.N.D.
SURFACE PREP: SSPC-SP 3
FINISH: NONE
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.
ALL COPIES TO HAVE 1/2" MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY
MEMBERS ARE TO BE ERRECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E DWG
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

PRINT RECORD	DATE	BY	CHKD
1			

JOB NO. 403
DATE JAN 14 2015
DRAWN BY ME
CHECKED BY GDI


REV#	DATE	DESCRIPTION

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4388 ROUTE 422
PLATTSBURGH, N.Y. 12001
518-561-0061

ENCMPASS DEVELOP
DESIGN CONSTRUCTION

AKWESASNE MOHAWK
HOTEL
873 STATE HIGHWAY 37
AKWESASNE NY

sheet
11C15



ONE BEAM 11B69

W	201 3/16 x 3/8
F	6 1/2 x 3/16
K	1 1/4 x 7/8



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
11	1	ONE	11B69	BEAM				1732
		1	11B69	W21x50	34	3 3/4	A992	1705
		1	w14	W5x19	1	6	A992	28
				FIELD BOLTS				
		3	1	Dia A325N	0	2	1HD WASH	
		10	3/4	Dia A325N	0	2 3/4	1HD WASH	
		14	3/4	Dia A325N	0	2 1/2	1HD WASH	
		6	3/4	Dia A325N	0	2	1HD WASH	
Total weight :								

HOLES: 13/16 " DIA U.N.D.
SURFACE PREP: SSPC-SP 3
FINISH: NONE
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.
ALL COPIES TO HAVE 1/2" MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY
MEMBERS ARE TO BE ERECTED SO THAT MARK END IS IN THE SAME LOCATION AS ON THE E DWG
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

PRINT RECORD	DATE	BY	CHECKED BY
1			

JOB NO. 403
DATE JAN 14 2015
DRAWN BY ME
CHECKED BY GDI


REV#	DATE	DESCRIPTION

JEFFORDS
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4388 ROUTE 422
PLATTSBURGH, N.Y. 12501
518-561-0061

customer
ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project
AKWESASNE MOHAWK
HOTEL
873 STATE HIGHWAY 37
AKWESASNE NY

sheet
11B69



BILL OF MATERIAL							
LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH		WEIGHT
					FT.	IN.	TOTAL
11	1	ONE	11B65	BEAM			257
		1	11B65	W24x62	2	10 5/8	177
		1	p50	PL 1/2 x 20 3/4	1	11 1/4	56
		1	p126	PL 1/2 x 7 3/16	0	9	7
		1	p22	PL 1/2 x 6	1	5 1/2	15
		2	p433	PL 1/4 x 2 3/4	0	7 3/4	3
				FIELD BOLTS			
		10		3/4 Dia A325N	0	2	1HD WASH
Total weight :							
HOLES: 13/16" DIA U.N.D.							
SURFACE PREP: SSPC-SP 3							
FINISH: NONE							
ELECTRODES: E70XX-(LOW HYDROGEN)							
GENERAL NOTES:							
ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.							
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.							
ALL COPIES TO HAVE 1/2" MINIMUM RADIUS.							
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY							
MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E DWG							
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.							

PRINT RECORD

1

11B65

job no. 403

date Jan 14 2015

drawn by

checked by

revisions

description

rev#

date

customer

ENCOMPASS DEVELOP

DESIGN CONSTRUCTION

project



AKWESASNE MOHAWK HOTEL

873 STATE HIGHWAY 37

AKWESASNE NY

sheet

11B65



W	$24\frac{1}{8} \times 1\frac{1}{2}$
F	$9 \times 3\frac{3}{4}$
K	$11\frac{1}{16} \times 1\frac{1}{8}$

[illegible]

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 3
FINISH: **NONE**
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL 1/4".
ALL VERTICAL SPACING OF HOLES TO BE 3" 1/4".
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS		
rev#	date	description

PRINT RECORD			
	I	FAB	4.17.1
job no.	4503		
date	Jan 14 201		
drawn by	MC		
checked by	GDI		

customer


ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project
AKWESASNE MOHAWK
HOTEL
873 STATE HIGHWAY 37
AKWESASNE, NY

**DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396**

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

11B42

[illegible]

sheet

4B70

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 3
FINISH: NONE
ELECTRODES: E70XX-(LOW HYDROGEN)


GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.


CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL
IS OBTAINED FROM JEFFERDS STEEL AND ENGINEERING COMPANY

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E DWG


ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE
HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT





rev.	date	description	revisions	job no. 4503	date Jan 14 2015	drawn by RC	checked by GRI	print record
1								




4 B 6 7



[illegible]


[illegible]

[illegible]

4B49	sheet	project	AKWESASNE MOHAWK HOTEL 873 STATE HIGHWAY 37 AKWESASNE NY	customer	ENCOMPASS DEVELOP DESIGN CONSTRUCTION	 STEEL AND ENGINEERING COMPANY P.O. BOX 40-4358 ROUTE 422 PLATTSBURGH, N.Y. 12901 315-561-4061	revisions	rev.#	date	description	job no. 5500 date Jan 14 2015 drawn by KC checked by GDI	print record	1	APP/FAB 3.11.12
------	-------	---------	--	----------	--	---	-----------	-------	------	-------------	---	--------------	---	-----------------



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396



W	$25\frac{1}{4} \times 3\frac{3}{4}$
F	$12\frac{7}{8} \times 15\frac{1}{16}$
K	$2\frac{1}{4} \times 15\frac{1}{16}$

LIFT	LIFT	NO. OF	PIECE		LENGTH			WEIGHT
NO.	QTY.	PIECES	MARK	MATERIAL	FT.	IN.	REMARKS	TOTAL
4	1	ONE	4B39	BEAM				4022
		1	4B39	W24x176	22	4 1/16	A992	3905
		1	a150	L4x3 1/2 x 1/2	1	7	A572-50	17
		1	a155	L4x3 1/2 x 1/2	1	7	A572-50	17
		1	a186	L4x3 1/2 x 5/16	2	11 1/2	A572-50	22
		1	a187	L4x3 1/2 x 5/16	2	11 1/2	A572-50	22
		1	p533	PL 3/4 x 11 3/4	1	1	A572-50	21
		6		1 Dia A325N	0	3 1/4	1HD WASH	10
		11		3/4 Dia A325N	0	2 1/2	1HD WASH	4028

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL W/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" W/N.
ALL COPES TO HAVE $\frac{1}{2}$ " MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS		
rev#	date	description

PRINT RECORD		
1	APP/FAB	5.11.1

project
AKWESASNE MOHAWK
HOTEL
873 STATE HIGHWAY 37
AKWESASNE, NY




DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

4B39

FIELD BOLTS



ONE BEAM 1B92

W 21 3/8 x 1/2
F 12 5/16 x 13/16
K 11 1/16 x 1 1/8



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 12-396

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
1	1	ONE	1B92	BEAM				2516
			1 1B92	W21x101	22	3 5/16	A992	2247
			1 p587	PL1x16 3/8	3	4	A572-50	164
			1 p570	PL 1/2 x 19 3/4	2	0 1/4	A572-50	52
			1 p671	PL 1/2 x 19 3/4	2	0 1/4	A572-50	52
				FIELD BOLTS				
			48	1 Dia A490SC	0	2 3/4	1HD WASH	
Total weight :								

HOLES: 13/16 " DIA U.N.D.
SURFACE PREP: SSPC-SP 2
FINISH: NONE
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL UNLESS NOTED.
ALL VERTICAL SPACING OF HOLES TO BE 3" UNLESS NOTED.
ALL COPIES TO HAVE 1/2" MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY
MEMBERS ARE TO BE ERRECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE E DWG
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PC MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. IN THE NON-PC MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

PRINT RECORD					
APP 123					

JOB NO. 403	DATE JAN 14 2015
DRAWN BY ME	CHECKED BY -



REV#	DATE	DESCRIPTION

JEFFORDS
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4388 ROUTE 422
PLATTSBURGH, N.Y. 12501
518-561-1061

customer
ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project
AKWESASNE MOHAWK
HOTEL
873 STATE HIGHWAY 37
AKWESASNE NY

sheet
1B92



W	8 1/8 x 1/4
F	4 x 5/16
K	13/16 x 5/8

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.	REMARKS	WEIGHT TOTAL
1	1	ONE	1B57	BEAM			280
		1	1B57	W8x15	10 5 3/8	A992	155
		1	w49	W8x15	5 5 5/8	B1E A992	82
		1	bp11	BPL 1/4 x 9 1/16	5 6 1/2	BENT A572-50	43
				FIELD BOLTS			
		2		3/4 Dia A325N	0 1 3/4	1HD WASH	
							280

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.
MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2016
drawn by TC
checked by GDI

PRINT RECORD

APP-1-4		
FAB 2-22		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1B57



ONE COLUMN 1C13

W	$5\frac{7}{8} \times \frac{3}{16}$
F	$3\frac{15}{16} \times \frac{3}{16}$
K	$1\frac{1}{16} \times \frac{9}{16}$

BILL OF MATERIAL

[illegible]

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: **PPG COATING 94-232**
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

[illegible]

job no. 4497
date Feb 22 201
drawn by TC
checked by GDI

PRINT RECORD

APP-1-4		
FAB 2-22		

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY



**DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390**

Jeffords
STE
P.

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y 12901
518-561-4061

1013



W	$5\frac{7}{8} \times 3\frac{1}{16}$
F	$3\frac{15}{16} \times 3\frac{1}{16}$
K	$1\frac{1}{16} \times 9\frac{9}{16}$

[illegible]

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: **PPG COATING 94-232**
ELECTRODES: E70XX-(LOW HYDROGEN)

REVISIONS

[illegible]

customer



ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

1024

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061



BILL OF MATERIAL

LIFT	LIFT	NO. OF	PIECE		LENGTH			WEIGHT
NO.	QTY.	PIECES	MARK	MATERIAL	FT.	IN.	REMARKS	TOTAL
		ONE	1F1	FRAME				347
		1	c559	C4x5.4	22	5½	A572-50	121
		1	p298	PL ¼x1 ¾ ₁₆	0	4	A572-50	0
		1	c274	C4x5.4	6	8 9 ₁₆	A572-50	36
		10	p5	PL ½x3	0	10	A572-50	41
		1	c273	C4x5.4	6	8¾	A572-50	36
		1	c272	C4x5.4	6	8¾	A572-50	36
		1	c271	C4x5.4	6	8¾	A572-50	36
		1	c270	C4x5.4	6	8¾	A572-50	3436
		10		¾ Dia A325N	0	1¾	1HD WASH	6

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: **PPG COATING 94-232**
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

[illegible]

job no. 4497
date Feb 22 201
drawn by TC
checked by CHECKER

PRINT RECORD

APP-1-6		
APP-2-9		

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY




**DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390**

Jeffords
STEEL
P.O.


STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F1



ONE FRAME 1F10

FIELD BOLTS:
(10) 3/4" DIA. A325N x 1 1/2 1HD. WASH.



Section A-A
1F10

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.	REMARKS	WEIGHT TOTAL
		ONE	1F10	FRAME			463
		1	c344	C6x8.2	22 8 3/8	A572-50	186
		1	p222	PL 1/4 x 1 15/16	0 6	A572-50	1
		1	c24	C6x8.2	5 5 5/16	A572-50	44
		1	c22	C6x8.2	5 6 1/2	A572-50	45
		1	c27	C6x8.2	5 7 11/16	A572-50	45
		1	c32	C6x8.2	5 8 15/16	A572-50	46
		1	c35	C6x8.2	5 10 1/8	A572-50	47
		1	c37	C6x8.2	5 11 5/16	A572-50	463
		1	p177	PL 1/2 x 3	0 3	A572-50	1

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2014
drawn by TC
checked by GDI

PRINT RECORD

APP-1-6		
FAB 2-14		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F10



Section A-A
1F11

[illegible]

HOLES: 13¹⁶" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: **PPG COATING 94-232**
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERCTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS ON THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

[illegible]



project
AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY



**DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390**

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1 F 1 1



Section A-A
1F12

ONE FRAME 1F12

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
		ONE	1F12	FRAME				463
		1	c425	C6x8.2	22	8 1/8	A572-50	186
		1	p222	PL 1/4x1 5/16	0	6	A572-50	1
		1	c24	C6x8.2	5	5 5/16	A572-50	44
		1	c22	C6x8.2	5	6 1/2	A572-50	45
		1	c27	C6x8.2	5	7 11/16	A572-50	45
		1	c32	C6x8.2	5	8 15/16	A572-50	46
		1	c35	C6x8.2	5	10 1/8	A572-50	47
		1	c37	C6x8.2	5	11 5/16	A572-50	463
		1	p177	PL 1/2x3	0	3	A572-50	1

HOLES: 1 3/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2014
drawn by TC
checked by GDI

PRINT RECORD

APP-1-6		
FAB 2-14		




DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer
ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project
AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F12



ONE FRAME 1F13



Section A-A
1F13

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
		ONE	1F13	FRAME				420
		1	c278	C6x8.2	22	5 1/2	A572-50	184
		1	c24	C6x8.2	5	5 5/16	A572-50	44
		1	c46	C6x8.2	6	2 15/16	A572-50	50
		1	c40	C6x8.2	6	0 1/2	A572-50	49
		1	c35	C6x8.2	5	10 1/8	A572-50	47
		1	c27	C6x8.2	5	7 3/4	A572-50	46
				FIELD BOLTS				420

10

3/4 Dia A325N

0

1 1/2

1HD WASH

HOLES: 1 3/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2016
drawn by TC
checked by GDI

PRINT RECORD

APP-1-6		
FAB 2-14		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords


STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F13



ONE FRAME 1F14

(REF. E3)



Section A-A

1F14

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
		ONE	1F14	FRAME				761
		1	c564	C4x5.4	38	6	A572-50	208
		7	c336	C4x5.4	5	2	A572-50	192
		6	p296	PL 3/4x8 3/16	0	9 3/16	A572-50	92
		6	p297	PL 3/4x7 3/16	0	8 15/16	A572-50	78
		1	a1428	L3x3x1/4	38	10	A572-50	190
								761

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2016
drawn by TC
checked by GDI

PRINT RECORD

APP-1-6		
APP-2-9		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION



project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F14



Section A-A
1F3

ONE GROUP MEMBER 1F3

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.	REMARKS	WEIGHT TOTAL
		ONE	1F3	GROUP MEMBER			340
		1	c341	C4x5.4	22 5 3/4	A572-50	121
		1	c246	C4x5.4	4 7	FIELD/APPL VERIFY A572-5024	
		12	p5	PL 1/2x3	0 10	A572-50	49
		1	c247	C4x5.4	4 7	FIELD/APPL VERIFY A572-5024	
		1	c248	C4x5.4	4 7	FIELD/APPL VERIFY A572-5024	
		1	c249	C4x5.4	4 7	FIELD/APPL VERIFY A572-5024	
		1	c250	C4x5.4	6 2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c251	C4x5.4	6 2 3/4	FIELD/APPL VERIFY A572-5033	

11

3/4 Dia A325N

0 2

2HD WASH

8

HOLES: 1 3/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPIES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2011
drawn by TC
checked by CHECKER

PRINT RECORD

APP-1-6		
APP-2-9		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F3



ONE FRAME 1F4

BILL OF MATERIAL (REF. E4)							
LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.	REMARKS	WEIGHT TOTAL
		ONE	1F4	FRAME			319
		1	c337	C4x5.4	17 6 ⁵ / ₈	A572-50	95
		1	c210	C4x5.4	6 8 ³ / ₄	FIELD/APPL VERIFY	A572-5036
		1	c211	C4x5.4	6 8 ³ / ₄	FIELD/APPL VERIFY	A572-5036
		1	c212	C4x5.4	6 8 ⁹ / ₁₆	FIELD/APPL VERIFY	A572-5036
		10	p5	PL 1/2x3	0 10	A572-50	41
		1	p298	PL 1/4x15 ⁵ / ₈	0 4	A572-50	0
		1	c277	C4x5.4	6 8 ⁹ / ₁₆	A572-50	36
		1	c213	C4x5.4	6 8 ⁹ / ₁₆	FIELD/APPL VERIFY	A572-5036
		8		3/4 Dia A325N	0 2	2HD WASH	6

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:
ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS		
rev#	date	description

job no.	4497	PRINT RECORD	
date	Feb 22 201	APP-1-6	
drawn by	TC	APP-2-9	
checked by	CHECKER		

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION


project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY


DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F4



ONE FRAME 1F5



BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.	REMARKS	WEIGHT TOTAL
		ONE	1F5	FRAME			347
		1	c341	C4x5.4	22 5 ³ / ₄	A572-50	121
		1	c269	C4x5.4	6 8 ⁹ / ₁₆	A572-50	36
		10	p5	PL 1 ¹ / ₂ x3	0 10	A572-50	41
		1	c268	C4x5.4	6 8 ³ / ₄	A572-50	36
		1	c267	C4x5.4	6 8 ³ / ₄	A572-50	36
		1	c266	C4x5.4	6 8 ³ / ₄	A572-50	36
		1	c264	C4x5.4	6 8 ⁹ / ₁₆	A572-50	36
		10		3 ¹ / ₄ Dia A325N	0 13 ¹ / ₄	1HD WASH	347 6

HOLES: 1³/₁₆" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1¹/₂" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2016
drawn by TC
checked by CHECKER

PRINT RECORD

APP-1-6		
APP-2-9		



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION



project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F5



BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
		ONE	1F6	FRAME				577
		1	c560	C4x5.4	22	8 1/8	A572-50	122
		1	c226	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c227	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c228	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c229	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c230	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		1	c232	C4x5.4	6	2 3/4	FIELD/APPL VERIFY A572-5033	
		12	p5	PL 1/2x3	0	10	A572-50	57 49

1	p298	PL 1/4x1 9/16	0	4	A572-50	0
6	c1	C4x5.4	6	2 3/4	A572-50	199

HOLES: 1 3/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS

rev#	date	description

job no. 4497
date Feb 22 2016
drawn by TC
checked by CHECKER

PRINT RECORD

APP-1-6		
APP-2-9		

customer

ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY





DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

Jeffords

STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F6



Section A-A
1F8

ONE FRAME 1F8

BILL OF MATERIAL

LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT.	IN.	REMARKS	WEIGHT TOTAL
		ONE	1F8	FRAME				437
		1	c278	C6x8.2	22	5 1/2	A572-50	184
		1	c53	C6x8.2	6	5 5/16	A572-50	52
		1	p177	PL 1/2 x 3	0	3	A572-50	1
		1	c40	C6x8.2	6	0 1/2	A572-50	49
		1	c43	C6x8.2	6	1 11/16	A572-50	49
		1	c46	C6x8.2	6	2 15/16	A572-50	50
		1	c50	C6x8.2	6	4 1/8	A572-50	51
								437

FIELD BOLTS:
(10) 3/4" DIA. A325N x 1 1/2 1HD. WASH.

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:

ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.

CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS
PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL
AND ENGINEERING COMPANY.

MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME
LOCATION AS ON THE ERECTION DRAWING.

ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END,
INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR
SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE
HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS		
rev#	date	description

PRINT RECORD	
APP-1-6	
FAB 2-14	

job no. 4497
date Feb 22 2014
drawn by TC
checked by GDI



DRAWINGS PREPARED BY,
GLOBAL DETAILING, INC.
JOB # 11-390

customer
ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project
AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

Jeffords
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F8

FIELD BOLTS


10

3/4 Dia A325N

0

1 1/2

1HD WASH



BILL OF MATERIAL							
LIFT NO.	LIFT QTY.	NO. OF PIECES	PIECE MARK	MATERIAL	LENGTH FT. IN.		WEIGHT TOTAL
		ONE	1F9	FRAME			438
		1	c437	C6x8.2	22	5 3/4	A572-50 184
		1	c53	C6x8.2	6	5 5/16	A572-50 52
		1	p177	PL 1/2 x 3	0	3	A572-50 1
		1	c40	C6x8.2	6	0 1/2	A572-50 49
		1	c43	C6x8.2	6	1 11/16	A572-50 49
		1	c46	C6x8.2	6	2 7/8	A572-50 51
		1	c50	C6x8.2	6	4 1/8	A572-50 51
							438

FIELD BOLTS:
(10) 3/4" DIA. A325N x 1 1/2 1HD. WASH.

HOLES: 13/16" DIA U.N.O.
SURFACE PREP: SSPC-SP 2
FINISH: PPG COATING 94-232
ELECTRODES: E70XX-(LOW HYDROGEN)

GENERAL NOTES:
ALL DIMENSIONS FROM END OF MAIN MATERIAL U/N.
ALL VERTICAL SPACING OF HOLES TO BE 3" U/N.
ALL COPES TO HAVE 1/2" MINIMUM RADIUS.
CHARGES FOR CORRECTIVE WORK WILL NOT BE HONORED UNLESS PREVIOUS APPROVAL IS OBTAINED FROM JEFFORDS STEEL AND ENGINEERING COMPANY.
MEMBERS ARE TO BE ERECTED SO THAT MARKED END IS IN THE SAME LOCATION AS ON THE ERECTION DRAWING.
ON SHOP BOLTED CLIP ANGLES ON BEAMS: ON PIECE MARK END, INSERT SHOP BOLTS SO THE HEAD OF THE BOLT IS ON THE NEAR SIDE OF BEAM. ON THE NON-PIECE MARK END, INSERT BOLTS SO THE HEAD OF THE BOLT IS ON THE FAR SIDE OF BEAM.

REVISIONS		
rev#	date	description

job no.	4497
date	Feb 22 2014
drawn by	TC
checked by	GDI

PRINT RECORD			
APP-1-6			
FAB 2-14			

customer


ENCOMPASS DEVELOP
DESIGN CONSTRUCTION

project

AKWESASNE MOHAWK
CASINO
873 STATE HIGHWAY 37
AKWESASNE, NY

JEFFORDS
STEEL AND ENGINEERING COMPANY
P.O. BOX 40-4398 ROUTE #22
PLATTSBURGH, N.Y. 12901
518-561-4061

1F9



sheet
1T2a

